

Domestic waterwork pump PM 15/150, three phase, 4 bar



The pump, which is assembled on site, is type tested and consists of the following parts: Pumpmeister piston pump with built in membrane safety valve (type tested), electric motor, galvanized pressure vessel, pressure switch programmed from 0.2 to 3.5 bar, pressure gauge, ventilation machine, completely closed belt guard made from plastic for your safety. A motor protection switch must be provided on site.

Details

Flow rate Q in m³/h: max. 1,50

Motor performance in kW (P2): 0,37

Total head H in m WS: max. 60

Field of application

- > Water supply
- > Agriculture
- > Rainwater utilisation
- > Industry
- > Shipping

Miscellaneous

- > Saline water
- > Higher performances

Downloads

- [General operation manual](#)
- [Spare parts list](#)
- [Catalogue page](#)
- [EC declaration of conformity](#)
- [Dimensional drawing](#)